

TO: 1052290  
STATE CORPORATION COMMISSION

9-8

API NUMBER 15-165-21,551-0000  
C E/2 NW SE SEC. 4, T 19 S, R 17 W

CONSERVATION DIVISION - PLUGGING SECTION 1980 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1650 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME MOORE "L" WELL # 1

TECHNICIAN'S PLUGGING REPORT COUNTY RUSH 126.04

OPERATOR LICENSE # 5393 WELL TOTAL DEPTH 3878 FEET

OPERATOR: A.L. ABERCROMBIE PRODUCTION CSG: SIZE 5 1/2 " FEET 3869

NAME AND RT. 1 BOX 56 SURFACE CASING: SIZE 8 5/8" FEET 480'

ADDRESS GREAT BEND, KS 67530

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SWD WELL  D/A

OTHER WELL AS HEREINAFTER INDICATED \_\_\_\_\_

PLUGGING CONTRACTOR MIKE'S TESTING & SALVAGE, INC LICENSE NUMBER 31529

ADDRESS PO BOX 467, CHASE, KS 67524

COMPANY TO PLUG AT: HOUR: 12:00 PM DAY: 08 MONTH: 09 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM MANNY BOATRIGHT

(COMPANY NAME) MIKE'S TESTING & SALVAGE, INC (PHONE) 316-938-2943

WERE: PERFS AT 3869 TO 3878

1ST PLUG SAND TO 3800' & 5 SX CEMENT, 2ND PLUG AT 1250' WITH 10 SX GEL & 50 SX CEMENT

3RD PLUG AT 700' WITH 40 SX CEMENT, 4TH PLUG AT 500' WITH 40SX CEMENT,

5TH PLUG AT 40' WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL  PART  NONE

OPERATIONS COMPLETED: HOUR: 3:15 PM DAY: 08 MONTH: 09 YEAR: 1998

ACTUAL PLUGGING REPORT \_\_\_\_\_

1ST PLUG SAND TO 3810' & 5 SX CEMENT, 2ND PLUG AT 1230' WITH 10 SX GEL & 50 SX CEMENT,

3RD PLUG AT 700' WITH 40 SX CEMENT, 4TH PLUG AT 500' WITH 40 SX CEMENT,

5TH PLUG AT 40' WITH 10 SX CEMENT.

RECEIVED  
SEP 17 1998  
RICHARD LACEY  
TECHNICAL SUPERVISOR

REMARKS: 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1800' OF 5 1/2" CASING.  
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (THE OPERATOR) RESERVE THIS PLUGGING.

SIGNED Richard M. Lacey  
(TECHNICIAN) FORM CP-2/3

INVOICED  
DATE SEP 17 1998  
INV. NO. 51308