

To: 1126834 9-27
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 4629
Operator: Brito Oil Company, Inc.
Name:
Address 200 E. 1st, Ste. 208
Wichita, KS 67202

API NUMBER 15- 165-21,634 - 0000
NW SE SE, SEC. 4, T 19 S, R 17 W
990 feet from S section line
990 feet from E section line
Lease Name Owens Well # 1-4
County Rush
Well Total Depth 3872 - 125.84 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 228

Abandoned Oil Well ☒ Gas Well ☐ Input Well ☐ SWD Well ☐ O&A ☐
never produced
Other well as hereinafter indicated

Plugging Contractor Brito Oil Co. License Number 4629
Address 200 E. 1st, Ste. 208, Wichita, KS 67202

Company to plug at: Hour: 9:30 a.m. Day: 27 Month: 9 Year: 19 93

Plugging proposal received from Ralph Brito
(company name) Brito Oil Company (phone) 316-263-8787

were: 5 1/2" at 3864' w/100 sx cement, Open hole 3864-3872', DV @ 1216', cement circulated
1st plug pump in 5 1/2" casing with 200 lbs. hulls and 285 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All ☒ Part ☐ None ☐
Operations Completed: Hour: 11 a.m. Day: 27 Month: 9 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug pumped in 5 1/2" casing with 200 lbs. hulls and 285 sx cement.
Pumping pressure 0-1000 psi and shut in 500 psi.

Used 65/35 Pozmix 8% gel by Allied. No casing recovery.
If additional description is necessary, use BACK of this report.
Observe this plugging.
INVOICED 10-7-93
DATE 10-7-93
INV. NO. 38891
Signed Duane Rankin
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
OCT 06 1993
CONSERVATION DIVISION
Wichita, Kansas