

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 16 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Vernon W. Reid d/b/a G & R Production Company

Complete Address Drawer 2041 Wichita, Kansas 67201

Lease Name Givens Well No. 2

Location N/2 SE Sec. 19 Twp. 22 Rge. (E) (W) 19

County Pawnee Total Depth 4446'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Ralph Comstock Pipe Pulling

Address Stafford, Kansas 67578 License No. 490

Operation Completed: Hour 2 P Day 15 Month 11 Year 1972

The above well was plugged as follows:

Total Depth 4446' 8 5/8 csg set at 327' cwc 225 sk.

4 1/2 csg set at 4444' cw 100 sk cmt.

4 1/2 csg perf. (4338-4346)

Filled 4 1/2 csg W/sd (4300-4446) dumped 4 sk cmt W/dump bailer. (4260-4300)

Well had been squeezed - Recovered 256' of 4 1/2 csg.

Set rock bridge at 256' & filled to surface with 3 yds readymix cmt.

I hereby certify that the above well was plugged as herein stated.

Signed: Geo. J. Messing
Well Plugging Supervisor

DATE 11/16/72
INV. NO. 6640-W