

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -165-20, 752-0000 (of this well)

Operator's Full Name EUWER PETROLEUM

Complete Address 110 NORTH MARKET - SUITE 206 WICHITA, KANS

Lease Name WEIGAND Well No. II

Location SE-SE-NE Sec. 3 Twp. 18 Rge. 18 (E) (W) W

County RUSH Total Depth 657 EL

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated LOST HOLE - SHID RIG

Plugging Contractor RAINS & WILLIAMSON OIL CO. INC.

Address 435 PAGE COURT 220 WEST DOUGLAS, WICHITA ^{KS} License No.

Operation Completed: Hour 12:30 ^{PM} Day 16 TH Month FEB Year 1980

The above well was plugged as follows:

THE ABOVE WELL WAS DRILLED 12 1/2" HOLE FOR SP. (657 EL)
RAINS & WILLIAMSON LOST A PIECE OF PIPE (APPROX 5") IN HOLE
AT 657 EL -> PLUGGED HOLE - AND PLAN TO SHID RIG SEVERAL FT.
ORDERED 85 ^{SS} 50/50 Pozmix 4% GEL. (SPOTTED WITH DRILL STEM)
HEAVY MUD BETWEEN ALL PLUGS.

1ST PLUG @ 600 EL w/ 50^{SS} CMT
2ND PLUG @ 240 EL w/ 20^{SS} CMT
3RD PLUG. ^{SOLID BRIDGE} HULL'S -> @ 40 EL TO 10 w/ 10^{SS} CMT - 5^{SS} IN EXT HOLE
(CEMENTED BY ALLIED)

RECEIVED
FEB 20 1980
STATE CORPORATION COMMISSION

I hereby certify that the above well was plugged as herein stated.

Signed: Mervin Schmidt
Well Plugging Supervisor

INVOICED
DATE 2-22-80
INV. NO. 1571-W