

KANSAS

*22*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
APR 4 - 1972  
4-4-72  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Pickrell Drilling Company

Complete Address 705 Fourth National Bank Bldg., Wichita, Kansas

Lease Name Bryant "A" Well No. 1

Location C NE ~~SW~~ Sec. 16 Twp. 18 Rge. (E) (W) 20

County Rush Total Depth 4115'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Co. Tools

Address        License No.       

Operation Completed: Hour 11:30 P Day 1 Month 4 Year 1972

The above well was plugged as follows:

RTD 4115' 8 5/8 csg set at 254' cwr. Cmt. Mat. 50-50 poz cmt W/4% added gel.  
Gunned pits, circulated heavy mud, set cementing plug at 450' and displaced 50 sk  
cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 25 sk cmt  
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to  
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Mosey  
Well Plugging Supervisor

DATE 4-4-72

INV. NO. 5491-10