

15-165-20345-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

RECEIVED
STATE CORPORATION COMMISSION

SEP 2 1970

CONSERVATION DIVISION AGENT'S REPORT

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Rains & Williamson Oil Company, Inc.
Complete Address 1425 Wichita Plaza Wichita, Kansas
Lease Name Bannister Well No. 1
Location NE NW SE Sec. 28 Twp. 18 Rge. (E) (W) 20
County Rush Total Depth 4230'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Co. Tools
Address License No.
Operation Completed: Hour 10 A Day 1 Month 9 Year 1970

The above well was plugged as follows:

RTD 4230' 8 5/8 csg set at 250' cwc Cmt. Mat. 50-50 poz W/6% gel
Gunned pits, circulated heavy mud, set cementing plug at 500' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Masey

Well Plugging Supervisor

DATE 9/2/70

INV. NO. 2475-W