

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-22330-00-00
Spot: SWSWSWNE Sec/Twnshp/Rge: 23-15S-23W
2460 feet from N Section Line, 2450 feet from E Section Line
Lease Name: SHIRLEY B Well #: 1
County: TREGO Total Vertical Depth: 4290 feet

Operator License No.: 9860
Op Name: CASTLE RESOURCES, INC.
Address: BOX 87
SCHOENCHEN, KS 67667

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT		1700		150 SX CMT
PROD	5.5	4279		350 SX
SURF	8.625	212		150 SX
T1	2.875	3425		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/09/2013 8:30 AM
Plug Co. License No.: 34852 Plug Co. Name: NOBLE WELL SERVICE, LLC
Proposal Rcvd. from: BILLY BRINEY Company: CASTLES RESOURCES, INC. Phone: (785) 798-5116

Proposed
Plugging
Method:

Ordered 315 sx 60/40 pozmix 4% gel cement, 15 sx gel and 600 # hulls.

Plugging Proposal Received By: BRUCE BASYE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/09/2013 1:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

Ran tubing to 4250' and pumped 15 sx gel w/100 # hulls followed by 50 sx cement w/100 # hulls.
Pulled tubing to 2250' and pumped 120 sx cement w/200 # hulls.
Pulled tubing to 1100' and pumped 120 sx cement w/200 # hulls.
Cement circulated to pit.
POOH. Hooked to braden head and pumped 5 sx cement at 250 psi.
Hooked to 5 1/2" casing and pumped 20 sx cement at 300 psi, displaced valve w/fresh water and shut in.

GPS: 38.73330 -099.84731

RECEIVED
KANSAS CORPORATION COMMISSION
MAY 16 2013
CONSERVATION DIVISION
WICHITA, KS

Remarks: SWIFT SERVICES TICKET # 24757

Plugged through: TBG

District: 04

Signed

Ray A. Dinkel
6/29/13

(TECHNICIAN)

CM

MAY 10 2013