

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-20578-00-00
Spot: W2NENENE Sec/Twnshp/Rge: 6-29S-11W
4960 feet from S Section Line, 358 feet from E Section Line
Lease Name: ARMITSTEAD A Well #: 1
County: PRATT Total Vertical Depth: 2760 feet

Operator License No.: 33055
Op Name: KRUCKENBERG, GENE DBA CIRCLE K ✓
Address: 7317 NE STATE HWY K42
ISABEL, KS 67065

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	2744		WITH 200 SX CMT
SURF	8.625	302		WITH 250 SX CMT

ENTERPRISES

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/06/2013 12:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2634

Proposed Plugging Method: PUMP 5 SX CMT ON BOTTOM. BOND LOG TBG & MAKE DETERMINATION ON PLUGGING ORDERS.



Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/06/2013 2:20 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PUMPED 5 SX CMT DOWN TBG & DISPLACED TO 2600'. BOND LOG INDICATED SCATTERED CMT FROM 0-506'. PERFORATED 2 7/8" @ 570'. PUMPED 90 SX CMT DOWN 2 7/8". MAXIMUM PRESSURE 600 PSIG. SHUT IN PRESSURE 200 PSIG.

Perfs:

Top	Bot	Thru	Comments
2684	2690		

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 20 2013


CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

RECEIVED

MAY 15 2013

KCC DODGE CITY

Form CP-2/3

