

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-20589-00-00
Spot: NWSESENW Sec/Twnshp/Rge: 6-29S-11W
2997 feet from S Section Line, 2996 feet from E Section Line
Lease Name: ARMITSTEAD B Well #: 1
County: PRATT Total Vertical Depth: 2760 feet

Operator License No.: 33055
Op Name: KRUCKENBERG, GENE DBA CIRCLE K
Address: 7317 NE STATE HWY K42
ISABEL, KS 67065

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	2760	1513	WITH 175 SX CMT
SURF	8.625	299		WITH 250 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/07/2013 2:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2634

Proposed Plugging Method: PUMP 5 SX CMT ON BOTTOM. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 330' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/07/2013 4:00 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PUMPED 5 SX CMT DOWN TBG & DISPLACED TO 2600'. 1ST PLUG AT 620' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 310' WITH 50 SX CMT. 3RD PLUG AT 61' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2648	2690		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: TBG

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 20 2013

CONSERVATION DIVISION
WICHITA, KS

District: 01

Signed

Richard W. Lacey
5/30/13

(TECHNICIAN)

RECEIVED

MAY 15 2013

KCC DODGE CITY

AMY