

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-20465-00-01
Spot: NENE Sec/Twnshp/Rge: 3-24S-14W
4671 feet from S Section Line, 639 feet from E Section Line
Lease Name: PETROS Well #: 1
County: STAFFORD Total Vertical Depth: 4080 feet

Operator License No.: 34320
Op Name: LISSO ENERGY LLC
Address: PO BOX 465
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4080	1968	WITH 115 SX CMT
SURF	8.625	250		WITH 185 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/10/2013 8:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2634

Proposed Plugging Method: SAND BACK TO 3700' & 5 SX CMT. PLUG AT 880' WITH 10 SX GEL & 50 SX CMT. PLUG AT 280' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/10/2013 9:50 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SANDED BACK TO 3690' & PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. 1ST PLUG AT 890' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 280'. CIRCULATE TO SURFACE WITH 100 SX CMT. LAY DOWN REST OF CASING. HOLE & CELLAR STANDING FULL WITH CMT.

Perfs:

Top	Bot	Thru	Comments
4002	4012		
3750	3756		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

KCC WICHITA

MAY 22 2013

RECEIVED

District: 01

RECEIVED

MAY 16 2013

KCC DODGE CITY

Signed

Stephen J. Pfeifer
5/30/13 (TECHNICIAN)

ADD