

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-16711-00-00
Spot: S2S2N2NE Sec/Twnshp/Rge: 35-34S-13W
1120 feet from N Section Line, 1320 feet from E Section Line
Lease Name: STERLING RM Well #: 5
County: BARBER Total Vertical Depth: 4900 feet

Operator License No.: 31980
Op Name: LOTUS OPERATING COMPANY, L.L.C.
Address: 100 S MAIN STE 420
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	7	4896		WITH 200 SX CMT
SURF	8.625	200		WITH 225 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 05/13/2013 9:00 AM
Plug Co. License No.: 33939 Plug Co. Name: BLACKGOLD OILFIELD SERVICE LLC
Proposal Rcvd. from: ROBIN BROWN Company: LOTUS OPERATING Phone: (620) 546-4801

Proposed Plugging Method: RUN TBG IN & CMT OFF PERFS WITH 300 SX CMT. PER OPERATOR WISHES, PULL, LET SET, & TAG CMT. PERFORATE @ 600' & CIRCULATE CMT TO SURFACE. FILL 7" & 8 5/8" WITH CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: NONE
Date/Time Plugging Completed: 05/13/2013 10:30 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PLUGGED THE BOTTOM WITH 150# HULLS & 200 SX CMT. TAGGED CMT AT 3430'. PERFORATED AT 600' & PUMPED 200 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
4840	4850		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 20 2013

CONSERVATION DIVISION
WICHITA, KS

District: 01

Signed Steve Pfeifer
(TECHNICIAN)

RECEIVED

MAY 14 2013

KCC DODGE CITY