

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-00496-00-00
Spot: SWSNW Sec/Twnshp/Rge: 28-5S-20W
2970 feet from S Section Line, 3630 feet from E Section Line
Lease Name: VEHIGE B Well #: 2
County: PHILLIPS Total Vertical Depth: 3645 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3645		150 SX
SURF	8.625	163		125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/29/2013 11:30 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: RIC HOCKMAN Company: MURFIN DRILLING CO., INC. Phone: (785) 689-7567

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/800 # hulls.
Production perforations: 3592' - 3623'.
Casing leak at 3543' - 3551.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/29/2013 2:15 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perforated at 1750', 1100' and 160'.
Ran tubing to 3610' and pumped 200 sx cement w/300 # hulls.
Pulled tubing to 1750' and pumped 125 sx cement w/225 # hulls.
Pulled tubing to 1100' and pumped 93 sx cement to circulate cement to surface. Closed 5 1/2" casing and pumped 22 sx cement to circulate 8 5/8"x 5 1/2" annulus to surface.
Pulled all tubing and topped off 5 1/2" casing w/10 sx cement.

GPS: 39.58994N -099.58443 W

Perfs:

Top	Bot	Thru	Comments
3621	3623		
3617	3623		
3610	3612		
3608	3610		
3592	3612		

Remarks: SWIFT TICKET # 24403

Plugged through: TBG

KCC WICHITA

MAY 28 2013

RECEIVED

District: 04

Signed

Pat Bedore
5/20/13

(TECHNICIAN)

CM

MAY 02 2013