

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-19487-00-00
Spot: S2NENW Sec/Twnshp/Rge: 13-11S-18W
4290 feet from S Section Line, 3300 feet from E Section Line
Lease Name: HADLEY BC Well #: 2
County: ELLIS Total Vertical Depth: 3362 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	15.5	110		110 sx
PROD	7	3354		250 SX
SURF	10.75	1108		630 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/16/2013 9:30 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: STAN FROETSCHNER Company: MURFIN DRILLING CO., INC. Phone: (785) 483-1197

Proposed Plugging Method: Ordered 725 sx 60/40 pozmix 4% gel cement, 15 sx gel, 1000 # hulls, and 400 # c.c. on the side
Perforations: 1650' and 1000'

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/16/2013 2:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 3200' and pumped 15 sx gel followed by 100 sx cement w/2% cc in mixing water and 200 # hulls mixed in.
Pulled tubing to 1659' and pumped 200 sx cement w/300 # hulls.
Pulled tubing to 400' and pumped 75 sx cement.
Cement circulated to pit.
POOH. Hooked up to casing and pumped 10 sx cement @ 400 psi. Shut in.
Hooked up to braden head of 10 3/4" casing and pumped 5 sx cement at 150 psi. Shut in.
15 1/2" conductor pipe was cut orange peeled to 10 3/4". Was found to be full of cement.

GPS: 39.10020 -099.27039

Perfs:

Top	Bot	Thru	Comments
2966	3253		

Remarks: QUALITY CEMENTING TICKET # 6775

Plugged through: TBG

KCC WICHITA

MAY 28 2013

RECEIVED

District: 04

Signed

Ray Dinkel
5/30/13

(TECHNICIAN)

CM