

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-25939-00-00
Spot: SWSESWSE Sec/Twnshp/Rge: 13-13S-18W
110 feet from S Section Line, 1810 feet from E Section Line
Lease Name: GOTTSCHALK-POLIFKA UNIT Well #: 1
County: ELLIS Total Vertical Depth: 3800 feet

Operator License No.: 32875
Op Name: BOWLES, C. W. DBA CWB - CO.
Address: PO BOX 186
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PC		1408		210 SX CMT
PROD	4.5	3797		210 SX
SURF	8.625	223		150 SX
TI	2.375	3754		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/07/2013 4:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JAY PFEIFER Company: CWB-CO Phone: (785) 659-6013

Proposed Plugging Method: Ordered 325 sx 60/40 pozmix 4% gel cement; 700 # hulls.
DV Tool at 1408' w/210 sx cement.
Perforations-3643'-3646'; 3556'-3559'; 3542'-3544'; 3534'-3536'; 3592'-3596'
GPS: 38.91484 -099.26794
SW SE SW SE 128' FSL 1820' FEL

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/07/2013 5:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Quality rigged to 4 1/2" casing and pumped 285 sx cement w/500 # hulls mixed in to pressure with 100 psi and 100 psi shut in pressure.
Rigged to 8 5/8" casing and pumped 20 sx 60/40 pozmix to pressure with 100 psi and 100 psi shut in pressure.

Perfs:

Top	Bot	Thru	Comments
3634	3636		LANSING- KC
3592	3596		LANSING- KC
3556	3559		LANSING- KC
3542	3544		LANSING- KC
3534	3536		LANSING- KC

RECEIVED
KANSAS CORPORATION COMMISSION
MAY 16 2013
CONSERVATION DIVISION
WICHITA, KS

Remarks: RICH MCINTYRE QUALITY WELL SERVICE INC. TICKET # 5881

Plugged through: CSG

District: 04

Signed [Signature]
5/29/13 (TECHNICIAN)

CM

MAY 10 2013