

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-075-10044-00-00
Spot: NENESWSW Sec/Twnshp/Rge: 7-21S-40W
1250 feet from S Section Line, 1250 feet from W Section Line
Lease Name: MAXFIELD Well #: 1-7
County: HAMILTON Total Vertical Depth: 2809 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: 6200 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1245		
CIBP		2740		WITH 2 SX CMT
PROD	4.5	2809	0	WITH 75 SX CMT
SURF	8.625	388		WITH 250 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/30/2013 9:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0806

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/30/2013 2:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

Perfs:

CIBP @ 2740' WITH 2 SX CMT. CIBP @ 1245'. TEST CASING TO 700#. HOLDING.
PERFORATE @ 1200'. INJECTION RATE 1 1/2 BPM @ 1300 PSI. MIX & PUMP 80 SX
CMT WITH 25 SX CMT OUTSIDE CASING & 55 SX CMT INSIDE CASING.
PRESSURED INCREASED FROM 600# TO 1350#. SQUEEZED OFF. HOLDING 1100#.
NO CIRCULATION OR BLOW UP ANNULUS. PERFORATE @ 440' & CIRCULATE
CMT TO SURFACE WITH 150 SX CMT.

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 20 2013

CONSERVATION DIVISION
WICHITA, KS

Remarks: **COMPLIANCE ISSUE: DENIED TA HIGH FL** USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: CSG

District: 01

Signed

Ken Jehlik
5/30/13

(TECHNICIAN)

RECEIVED

MAY - 9 2013

KCC DODGE CITY

AM