

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-23906-00-00
Spot: E2NWNWNE Sec/Twnshp/Rge: 3-10S-21W
330 feet from N Section Line, 2145 feet from E Section Line
Lease Name: TRIBLE Well #: 12
County: GRAHAM Total Vertical Depth: 3985 feet

Operator License No.: 3553
Op Name: CITATION OIL & GAS CORP.
Address: 14077 CUTTEN RD PO BOX 690688
HOUSTON, TX 77269

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1785		650 sx cement

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/23/2013 12:00 AM
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.
Proposal Rcvd. from: KELLY BRANUM Company: DUKE DRILLING CO., INC. Phone: (785) 324-1414

Proposed Plugging Method: Ordered 255 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: MARVIN MILLS WitnessType: NONE
Date/Time Plugging Completed: 04/23/2013 2:30 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Perfs:

1st plug @3617 w/50 sx
2nd plug @1835 w/50 sx
3rd plug @1010 w/100 sx
4th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

RECEIVED
KANSAS CORPORATION COMMISSION
MAY 16 2013
CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY

Plugged through: DP

District: 04

Signed [Signature]
5/30/13 (TECHNICIAN) CM

MAY 07 2013