

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-047-00048-00-00
Spot: E2NENW Sec/Twnshp/Rge: 22-24S-16W
717 feet from N Section Line, 2306 feet from W Section Line
Lease Name: ZUERCHER Well #: 1
County: EDWARDS Total Vertical Depth: 4300 feet

Operator License No.: 5042
Op Name: EDMISTON OIL COMPANY, INC.
Address: 125 N MARKET STE 1130
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4292	2030	WITH 75 SX CMT
SURF	8.625	260		WITH 200 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/29/2013 10:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: SHANNON RAYBERN Company: EDMISTON OIL Phone: (620) 793-2672

Proposed Plugging Method: PUMP 30 SX CMT AT 4200'. PLUG AT 1060' WITH 15 SX GEL & 50 SX CMT. PLUG AT 290' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/29/2013 12:20 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

PUMP 250# HULLS & 30 SX CMT AT 4185'. 1ST PLUG AT 1060' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 290' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 30 SX CMT. CMT CIRCULATED & HOLE STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
4292	4300		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 13 2013

CONSERVATION DIVISION
WICHITA, KS

District: 01

RECEIVED
MAY - 3 2013
KCC DODGE CITY

Signed [Signature]
(TECHNICIAN)