

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-24953-00-00  
Spot: SESWSWSE Sec/Twnshp/Rge: 7-20S-13W  
120 feet from S Section Line, 2100 feet from E Section Line  
Lease Name: NICOLET TRUST Well #: 1-7  
County: BARTON Total Vertical Depth: 3675 feet

Operator License No.: 5056  
Op Name: F. G. HOLL COMPANY L.L.C.  
Address: 9431 E CENTRAL STE 100  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3662		125 SX
SURF	8.625	733	733	315 SX
T1	2.875	3615		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/13/2013 1:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: ROB LONG Company: F G HOLL Phone: (620) 793-0915

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: BRUCE BASYE WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/13/2013 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perforations. Topped with 5 sx cement.  
Cut casing at 2160'.  
Pulled casing to 1700' and pumped 170 sx cement w/300 # hulls.  
Pulled casing to 700' and circulated cement to surface w/175 sx cement.  
Pulled casing. Hole stayed full.

GPS: 38.32462 -098.80420

Perfs:

Top	Bot	Thru	Comments
3490	3510		ARBUCKLE

KCC WICHITA

MAY 28 2013

RECEIVED

Remarks: QUALITY WELL SERVICE

Plugged through: CSG

District: 04

Signed Bruce Rodie  
5/30/13 (TECHNICIAN)

CM

MAY 21 2013