

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-147-19025-00-01  
Spot: NWSWSENE Sec/Twnshp/Rge: 9-1S-18W  
3032 feet from S Section Line, 1151 feet from E Section Line  
Lease Name: IMM Well #: 1  
County: PHILLIPS Total Vertical Depth: 3480 feet

Operator License No.: 31070  
Op Name: EAGLE RIVER ENERGY CORPORATIO  
Address: 7060 S YALE # 702  
TULSA, OK 74136

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3431		
PROD	0.5	3455		
PROD	4.5	3466		150 SX
SURF	8	178		125 SX

Well Type: EOR UIC Docket No: E15214.3 Date/Time to Plug: 04/30/2013 9:30 AM  
Plug Co. License No.: 31569 Plug Co. Name: BACH, JASON DBA BACH OIL PRODUCTION  
Proposal Rcvd. from: JOHN MICKLE Company: EAGLE RIVER ENERGY CORP Phone: (620) 639-2035

Proposed Plugging Method: Ordered 250 sx 60/40 pozmix 4% gel cement w/400 # hulls.  
Junk in hole at 600'.  
Perforated at 1500'. Circulated with 550 sx cement.  
*Spent a week trying to get down well. Old tubing in well bore was swiss cheese.  
~~Cost too much to pull out.~~*

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/30/2013 12:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 850' and pumped 70 sx cement to circulate to surface.  
Pulled tubing. Hooked to 4 1/2" casing and pumped 180 sx cement w/400 # hulls. Max pressure 600 psi. Shut in pressure 450 psi.  
Hooked to 8 5/8" x 4 1/2" annulus and pressured to 200 psi immediately.

GPS: 39.98104N -099.35115W

Perfs:

Top	Bot	Thru	Comments
3407	3408		
3405	3410		
3350	3352		
3346	3348		
3336	3337		
3335	3338		
3326	3327		
3323	3328		
3306	3310		
3289	3410		

Remarks: ALLIED TICKET # 54190

Plugged through: TBG

KCC WICHITA

MAY 28 2013

RECEIVED

District: 04

Signed

*Pat Bedore*

(TECHNICIAN)

Cjm

02 2013

*cc to MIC 5/2/13  
6/10/13*