

State of Kansas



ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAY 2 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Rodie of Rains & Williamson has this date requested permission to plug the following described well:

Mr. Rodie guarantees payment of the plugging fee.

Operator's full Name: Walters Drlg & Mull Drlg

Complete Address: 400 Insurance Bldg., Wichita, Ks.

Lease Name: Bryant Well No. 1

Location: C SW SW Sec. 9 Twp. 18 Rge. (E)(W) 20

County: Rush Total Depth 4170 Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Rodie was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 600' and displace

70 sk cmt thru drill pipe. Heavy mud to 210' set cementing plug and

displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sk hulls and 10 sk cmt to base of cellar. Plug rat hole with

2 sk cmt.

Very truly yours,

Leo J. Massey
Conservation Division Agent