

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Owens of R & W Drlg. has this

date requested permission to plug the following described well:

Mr. Owens guarantees payment of the plugging fee.

Operator's full Name: Stelbar Oil Corp., Inc.

Complete Address: 200 W. Douglas, Suite 950, Wichita, Kansas

Lease Name: Frank Well No. 1

Location: NE NW SE Sec. 32 Twp. 18 Rge. (E)(W) 20

County: Rush Total Depth 4256' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Owens was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 50 sx cem plug at 500' thru drill

pipe. Heavy mud to 240' set 25 sx cem plug thru drill pipe. Heavy mud

to 40' set solid bridge & 10 sx cem plug to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

AUG 8 1975
8-8-75
CONSERVATION DIVISION
Wichita, Kansas

Very truly yours,

Leo F. Muzzey
Conservation Division Agent