

District Plugging Report

Operator License No: 101	String	Size	Depth	Pulled	Comments
Op Name: STATE OF KANSAS	SURF - Casing	6.250	20	0	EST.
Address 1: 130 S. MARKET	PROD - Casing	2.000	680	0	EST.
Address 2:					
City: WICHITA					
State: KS Zip Code: 67202					

Well Type: OG - Oil & Gas (OIL) UIC Docket No.: _____ Date/Time to Plug: 12/7/12 / _____
 Plug Co License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC.
 Proposal Rcvd from: MIKE KEPLEY Company Name: KWS Phone: (620) 431-8945

Proposed Plugging Report:

Pump portland cement from TD to surface. Perforate when not documented Alt.II

Plugging Proposal Received By: Jeff Fredricks / Frank Guilfoyle Witness Type: COMP - Complete 100%
Date/Time Plugging Completed: 12/7/12 / KCC Agent: Frank Guilfoyle

Actual Plugging Report:

Perfs:	Top	Bottom	Thru
	100	350	CSG - Casing

Clear trees from location. Run 1" and reamer to 375 ft. Pull pipe. Perforate well. Run 1" pipe and wash to 680 ft. Pump portland cement from TD to surface. Pull pipe and top off well. Run Packer to 20 ft and squeeze. Pull packer and top off well. Well plugged. Perforations at 350 ft, 200 ft, and 100 ft. Pump total of 70 sacks of portland cement. Well plugged.

KANSAS CORPORATION COMMISSION

~~JAN 04 2013~~

RECEIVED

Remarks	C# 11782. Control No. 20130039-004. GPS'ed by F.G. Reg. Sec.
---------	--

Plugged Thru: TBG - Tubing

Plugged Due to Compliance Issue: ☐ Yes ☒ No

District: 03

Frank G. Gough
(Technician)

Form: District Plugging Report –