

Kansas Corporation Commission

District Plugging Report

API Well Number: 15-125-02456-0000
 Spot: SWSESE Sec 13 Twp 33 S Rng 14 ☒ E / ☐ W
218 Feet from ☐ N / ☒ S Line of Section
745 Feet from ☒ E / ☐ W Line of Section
 GPS: Lat: 37.168490 Long: 95.822040 Date: 2/5/11
 Lease Name: Keith Schill (Stocker) Well #: SCH 01
 County: Montgomery Total Vertical Depth: 965 feet

Operator License No: <u>101</u>	String	Size	Depth	Pulled	Comments
Op Name: <u>STATE OF KANSAS</u>	<u>PROD - Casing</u>	<u>6.250</u>	<u>965</u>	<u>0</u>	<u>EST.</u>
Address 1: <u>130 S. MARKET</u>					
Address 2:					
City: <u>WICHITA</u>					
State: <u>KS</u> Zip Code: <u>67202</u>					

Well Type: OG - Oil & Gas UIC Docket No.: _____ Date/Time to Plug: 8/16/11 / _____
 Plug Co License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC.
 Proposal Rcvd from: MIKE KEPLEY Company Name: KWS Phone: (620) 431-8945

Proposed
Plugging
Report:

Fill well with cement from td to surface,

Plugging Proposal Received By: Tom Bilyeu Witness Type: PART - Partial
 Date/Time Plugging Completed: 8/16/11 / _____ KCC Agent: Tom Bilyeu

Actual Plugging Report: _____ Perfs: _____ Top _____ Bottom _____ Thru _____

Run 1" and swedge to 500 ft. Pull 1" out. Perforate well at 350 ft, 150 ft, and 75 ft. Run 1" and wash to 965 ft. Pump portland cement from TD to surface. pull pipe and top off well. Pump total of 218 sacks of cement. Well plugged.

75 350 TBG - Tubing

KANSAS CORPORATION COMMISSION
 OCT 01 2011
 RECEIVED

Remarks: 20110025-001. PO # 14300-0000000233. REG. SEC.

Plugged Thru: TBG - Tubing

Plugged Due to Compliance Issue: ☐ Yes ☒ No

District: 03

Tom Bilyeu
 (Technician)

Form: District Plugging Report - _____