

Kansas Corporation Commission

District Plugging Report

API Well Number: 15-073-23127-00-00

Spot: NENWNE Sec 23 Twp 26 S Rng 12 ☒ E / ☐ W

5132 Feet from ☐ N / ☒ S Line of Section

1712 Feet from ☒ E / ☐ W Line of Section

GPS: Lat: 37.778560 Long: 96.058110 Date: 8/9/11

Lease Name: Lois Roberts Well #: ROB 01

County: Greenwood Total Vertical Depth: 1440 feet

Operator License No: 101
Op Name: State of Kansas String SURF - Casing Size 8.000 Depth 110 Pulled 0 Comments From Intent
Address 1: 130 S. MARKET
Address 2:
City: WICHITA
State: KS Zip Code: 67202 -

Well Type: Oil UIC Docket No.: Date/Time to Plug: 2/12/13 /
Plug Co License No.: 3097 Plug Co. Name: K-W OIL WELL SERVICES, INC.
Proposal Revd from: Robert Kepley Company Name: K-W Phone: (620) 431-2285

Proposed
Plugging
Report:

Drill and wash to TD. Stage plugs, 500 ft to surface.

Plugging Proposal Received By: FRANK GUILFOYLE Witness Type: COMP - Complete 100%
Date/Time Plugging Completed: 2/12/13 / KCC Agent: FRANK GUILFOYLE, Tony Anderson

Actual Plugging Report: Perfs: Top Bottom Thru
Move in and set up drill rig. Gel pit water and keep gelled until done. Drill and wash through cave and wood to 810 ft. Pull drill steel and run 2 3/8" to 625 and hit cave. Wash to 960 ft and hit hard. Couldn't break through. Pull pipe and run drill steel in. Drill and wash to 1440 ft. Stage 5 barrel plugs at 1440 ft, 1375 ft, 1080 ft, and fill from 530 ft to surface. Pump total of 352 sacks of cement. Well plugged.

Remarks Contract # 11782. Cat III. Control # 20130028-001. GPS by Mike Heffern. Reg Sec.

Plugged Thru: DP - Drill Pipe

RECEIVED
KANSAS CORPORATION COMMISSION

Plugged Due to Compliance Issue: ☐ Yes ☒ No

District: 03

MAR 04 2013
CONSERVATION DIVISION
WICHITA, KS

Frank Guilfoyle
(Technician)

Form: District Plugging Report -