

1 040008

11-17-87

API NUMBER 15-165-21,387-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW NW SW, SEC. 32, T 17 S, R 17 (W) EX

1650 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6177

Lease Name Edwards Well # 1

Operator: Foxfire Exploration, Inc.
Name & Address: 1022 Union Center
Wichita, KS 67202

County Rush 119.11

Well Total Depth 3665 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 7 feet 1069

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Foxfire Drilling Company, Inc. License Number 8430

Address Box 133, Wakeeney, KS 67672

Company to plug at: Hour: 11:10 p.m. Day: 16 Month: 11 Year: 19 87

Plugging proposal received from Gary Fisher

(company name) Foxfire Drilling Company, Inc. (phone) 913-743-5337

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1090-1125' Elevation 2001'

1st plug at 1080' with 40 sx cement,

2nd plug at 550' with 25 sx cement,

3rd plug at 40-0' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 1 a.m. Day: 17 Month: 11 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 1080' with 40 sx cement,

2nd plug at 550' with 25 sx cement,

3rd plug at 40-0' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
11-18-87
NOV 18 1987

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED (If you did not observe this plugging.)

DATE 12-2-87
INV. NO. 19025

Signed Stephen J. Pfeifer (TECHNICIAN)

11-17 JAN 14 1988

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 10 16 87 month day year

API Number 15-165-21,387-0000

OPERATOR: License # 6177 Name Foxfire Exploration, Inc. Address 1022 Union Center City/State/Zip Wichita, Kansas 67202 Contact Person Gary Fisher (913)743-5654 Phone or D.C. Marchant (805)549-0690

SW NW SW Sec. 32 Twp. 17 S, Rg. 17 East X West 1650 Ft. from South Line of Section 4950 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 8430 Name Foxfire Drilling Co., Inc. City/State Box 133, Wakeeney, Kansas 67672 Well Drilled For Well Class: Type Equipment: X Oil SWD Infield X Mud Rotary Gas Inj Pool Est Air Rotary OWWO Expl X Wildcat Cable

Nearest lease or unit boundary line 330 feet County Rush Lease Name Edwards Well # 1 Ground surface elevation est. 2015 feet MSL Domestic well within 330 feet yes X no Municipal well within one mile yes X no Depth to bottom of fresh water 350 Depth to bottom of usable water 200 Surface pipe by Alternate 1 X 2 Surface pipe planned to be set 1100 Conductor pipe required N.A. Projected Total Depth 3625 feet Formation Perm. Sand

If OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications. Date 10/5/87 Signature of Operator or Agent D.C. Marchant Title President

For KCC Use: Conductor Pipe Required feet; Minimum Surface Pipe Required 420 feet per Alt. This Authorization Expires 3-23-88 Effective 9-23-87 Approved By 9-23-87 9-28-87

SW. NW. SW. Sec. 32. Twp. 17. S, Rg. 17. East X West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ 50' below surface pipe 20' below Anhy. 50sx feet depth with 40sx 40' on bridge 2nd plug @ 3rd plug @ Bathole 4th plug @ 5th plug @ (2) Rathole with

Handwritten notes: PUSHED Jerry Fisher TD 3665 FORMATION GRANITE W/SH SURFACE PIPE 7" @ 1069 ANHYDRITE 1090 ELEVATION 2001 STARTING TIME & DATE 11:10pm 11-16 COMPLETION TIME & DATE 1AM 11-17 1st PLUG 40' FT. W/ 40 SX 2nd PLUG @ 1080 FT. W/ 40 SX 3rd PLUG @ 550 FT. W/ 25 SX 4th PLUG @ 40-0 FT. W/ 10 SX RAT HOLE CIRCULATED W/ 15 SX MOUSE HOLE CIRCULATED W/ SX WATER WELL PLUGGED W/ SX CEMENT COMPANY Allied TECHNICIAN 60/40 ppg w/ 60 gal.

STATE COM. REGISTRATION COMMISSION 11-18-87 NOV 18 1987 WICHITA, KANSAS