

To: STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING SECTION
 200 COLORADO DERBY BUILDING
 WICHITA, KANSAS 67202

API NUMBER 15-165-01640-00-01

SWNWSE, Sec. 35, T 17 S, R 17 W

_____ feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5140

Lease Name Witt Well # 1

Operator: Frontier Oil Co
 Name & Address 1720 Kansas State Bank
Wichita Kansas 67202

County Rush
 Well Total Depth 3534 feet \$111,86

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1088

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number ~~6050~~ 6050

Address Box 176 Chase Kansas 67524

Company to plug at: Hour: 9:30am Day: 9 Month: December Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO Millard Kelso

(company name) Kelso Casing Pulling (phone) _____

were: To 1st plug the bottom with sand to 2575 +
dump 4sx cement. Then pump down 8 5/8"
surface pipe with 3sx bulls - 15gel - 50sx cement
- 10gel - 1sx bulls - 1 8 5/8" wiper plug - 125sx cement
using 60/40 pozmix 2% gel, 3% cc for cement

Signed Richard W. Lacey
 (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:20pm Day: 9 Month: December Year: 19 83

ACTUAL PLUGGING REPORT Plugged as proposed in the above paragraph

Maximum pump pressure 850 psi

Shut in pressure 600 psi

Allied pumped the cement

Recovered 2036' of 4 1/2" production casing

Remarks: _____

I hereby certify that the above plugging instructions were given as herein stated and that I did / ~~did not~~ observe this plugging.

INVOICED

DATE 1-6-84

INV. NO. 8082-W

Signed Richard W. Lacey
 (TECHNICIAN)