

120253

5-5

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 165-20,993 -0000

SW SW NW, SEC. 2, T 17 S, R 17 W/E  
2970 feet from S section line  
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3456

Lease Name Steitz-Decker Well # 4

Operator: AFG Energy, Inc.  
Name & Address P.O. Box 605  
Russell, KS 67665

County Rush 103.35  
Well Total Depth 3180 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8" feet 228

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ x Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor AFG Energy, Inc. License Number 3456

Address P.O. Box 605, Russell, KS 67665

Company to plug at: Hour: 9:30 a.m. Day: 5 Month: 5 Year: 19 89

Plugging proposal received from Terry Piesker

(company name) AFT Energy, Inc. (phone) 913-483-2627

were: 4 1/2" at 3153' PBTB 3118' Perfs at 3085-93' Hole in 4 1/2" casing at 480' in 1985  
DV 400-0' squeezed w/300 sx cement, cement circ.

1st plug pump 1 sx hulls, 40 sx cement, 9 sx gel, 100 sx cement down 4 1/2" casing.

Plugging Proposal Received by Richard W. Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11 a.m. Day: 5 Month: 5 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug pumped into 4 1/2" casing with 100 lbs. hulls, 40 sx cement and 9 sx gel, and 100 sx cement. Pumping pressure 0-1000# and shut in 900#.

2nd plug pumped in annulus 8 5/8" X 4 1/2" with 15 sx cement,

Pumping pressure 0-500 psi and shut in 500 psi.

RECEIVED  
STATE CORPORATION COMMISSION  
WICHITA, KANSAS

MAY 9 1989

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.  
(If additional description is necessary, use BACK of this form.)

INVOICED Observe this plugging.

DATE 5-10-89

Signed [Signature] (TECHNICIAN)

INV. NO. 24736