

To: 1 052109 15-165-35172-0000
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 6/1/62
C SW, SEC. 3, T 17 S, R 17 W/R
1320 feet from S section line
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3456
Operator: AFG Energy Inc.
Name & Address: P.O. Box 458
Hays, KS 67601

Lease Name McGill Well # 2
County Rush 118.07
Well Total Depth 3633 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 217

Abandoned Oil Well Gas Well Input Well SWD Well D&A
Other well as hereinafter indicated
Plugging Contractor Allied Cementing License Number
Address

Company to plug at: Hour: 10 a.m. Day: 20 Month: 2 Year: 19 97
Plugging proposal received from Ed Glassman
(company name) AFG Energy Inc. (phone) 913-625-6374

were: 4 1/2" at 3212' w/150 sx cement, PBSD 3195', Perfs at 3066-78', DV @ 1183' w/550 sx cement
1st plug fill 4 1/2" casing with cement.

Check backside.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None
Operations Completed: Hour: 10:50 a.m. Day: 20 Month: 2 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug pumped down 4 1/2" casing with 500 lbs. hulls and 225 sx cement.
Maximum pressure 900 psi and shut in 200 psi.
Pressured 8 5/8" X 4 1/2" annulus to 500 psi.

RECEIVED
2-24-97
3:57

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.
(If additional description is necessary, use BACK of this form.)

I (copy) observe this plugging.

Signed Richard W. Lacey
(TECHNICIAN)

INVOICED
DATE 2-25-97
INV. NO. 47657
2-20