

15-165-3046-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 162

C. Neff, Sec. 3, T 17 S, R 17 W 1/4

R

_____ feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5140

Lease Name MCGILL Well # 3

Operator: FRONTIER Oil Co.
Name & Address 1720 KANSAS ST BK Bldg,
WICHITA, KS 67202

County RUSH

Well Total Depth 3677 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 7/8 feet 212'

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing Co License Number _____

Address Box 31, Russell, KS 67665

Company to plug at: Hour: 10:00 AM Day: 12 Month: Jan Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO TOM CASEY

(company name) FRONTIER (phone) _____

were: Use 50/50 Pozmix, 4% gel - 3% CC & Pump
3 1/2" huls, 25 sf cmt, 10 sf gel, 4 1/2" plug & 60
sf cmt. Check the annulus cement.

Signed R. Barluttan
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 11:00 AM Day: 12 Month: Jan Year: 1983

ACTUAL PLUGGING REPORT Plugged as ordered.

Pumping pressure, max. 500# - Shut
in @ 100 #

Remarks: 8 7/8 set @ 135 sf cmt - 4 1/2" @ 3117 w/ 150 sf cmt
Perfs @ 3058 - 3066 - MSC Tool @ 1168 w/ 550 sf cmt
to surface - Topoka top @ 3064

I hereby certify that the above plugging instructions were given as herein stated

and that I (did / ~~did not~~) observe the plugging.

RECEIVED
STATE CORPORATION COMMISSION

1-14-83
JAN 14 1983

CONSERVATION DIVISION
Wichita Kansas

Signed R. Barluttan
(TECHNICIAN)

FORM CP-2/3
Rev. 9-82

INVOICED

DATE 2-10-83

INV. NO. 2420-W