

To: 1 20637
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

15-165-19020-0000 10-2 17
API NUMBER 15- Drill Completion Date 5/25/63

SW NE, SEC. 16, T. 17 S, R. 17 W/E

3300 feet from S section line

1980 feet from E section line

Lease Name Kleweno "A" Well # 1

County Rush 116.96

Well Total Depth 3599 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 212

TECHNICIAN'S PLUGGING REPORT

Operator License # 3456

Operator: AFG Energy, Inc.

Name & Address P.O. Box 605

Russell, KS 67665

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Lightning Well Service, Inc. License Number 3232

Address 615 W. Wichita Ave., Russell, KS 67665

Company to plug at: Hour: 10 a.m. Day: 2 Month: 10 Year: 19 91

Plugging proposal received from Terry Piesker

(company name) AFG Energy, Inc. (phone) 913-483-6213

work: 4 1/2" at 3598' w/275 sx cement, PBD 2820', Perfs at 3438-3064' (4 sets, all below PB)
DV @ 1219', cemented with 500 sx cement

1st plug run tubing to 2820' and fill with 60/40 Pozmix 6% gel.

RECEIVED
STATE CORPORATION COMMISSION
10-9-91
OCT 09 1991

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 2:30 p.m. Day: 2 Month: 10 Year: 19 91

ACTUAL PLUGGING REPORT CIBP set at 2820', ran tubing to 2814' and pumped 50 sx cement,
pulled tubing to 2000' and pumped 50 sx cement, pulled tubing to 1200' and circulated
cement. Total cement 210 sx. Layed down all tubing and pumped in 4 1/2" casing with 15 sx
cement. Pumping pressure 700 psi and shut in 500 psi.

Pumped 10 gallons water in 8 5/8" X 4 1/2" annulus, pressured to 700 psi and shut in 700 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.
(if additional description is necessary, use BACK of this form.)

I (and ~~XXXXXX~~) observe this plugging.

INVOICED

Signed Richard Lacey
(TECHNICIAN)

DATE 10-29-91

INV. NO. 33530