

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-162 ✓ R
C.NE4, Sec. 3, T 17 S, R 17 W1X
_____ feet from N/S section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5140

Lease Name McGill Well # 1

Operator: FRONTIER OIL CO.
Name & Address 1720 KANSAS STATE Bk. Bldg
WICHITA, KS 67202

County BUSH

Well Total Depth 3652 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 7/8 feet 210'

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing Co., Inc. License Number _____

Address Box 31, Russell, KS 67665

Company to plug at: Hour: 8:30 AM Day: 12 Month: JAN Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO TOM CASEY

(company name) FRONTIER (phone) 913-983-5503

were: Use 50/50 foam mix, 4 1/2 gal - 3% cc and pump 2 1/2
hills, 25 sq. cmt, 10 sq. gal, release plug
and then 50 sq. cmt, down 4 1/2 casing. Test
annular space to insure cementing to surface.

Signed R. Barlutton
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 9:30 AM Day: 12 Month: Jan Year: 19 83

ACTUAL PLUGGING REPORT well went on vacuum and another
40 sq. cmt. pumped. Top wire lined in afternoon &
had dropped to 210' below surface. Another 15 sq.
cmt. pumped to fill to surface. Max pressure
300#, shut-in press. 100#

Remarks: 8 7/8 set w/ 135 sq. cmt. - 4 1/2" casing set @ 3198 w/ 150 sq. cmt
Perfs. 3078'-3086' - MSC tool @ 1183
TOPEKA @ 3076 -

I hereby certify that the above plugging instructions were given as herein stated
and that I (did / ~~did not~~) observe this plugging.

RECEIVED
STATE CORPORATION COMMISSION
1-14-83
JAN 14 1983
CONSERVATION DIVISION
Wichita, Kansas

Signed R. Barlutton
(TECHNICIAN)

FORM CP-2/3
Rev. 9-82

INVOICED

DATE 2-10-83

INV. NO. 2419-w

Phone 913-483-2627, Russell, Kansas
 Phone 316-793-5861, Great Bend, Kansas

K-165-00328-0000

Phone Plainville 913-434-2812
 Phone Kiowa 316-825-4618

O I D

ALLIED CEMENTING CO., INC.

Home Office P. O. Box 31 Russell, Kansas 67665

NO 32229

Date	1-12-83	Sec.	Twp.	Range	Called Out	On Location	Job Start	Finish	
						8:15 AM	9:05 AM	10:15 AM	
Lease	Mc Gill	Well No.	# 1	Location	Letta 35 1/2 W S3	County	Rush	State	KS

Contractor

Type Job **Plug to Abandon**

Hole Size	T.D.
Csg. Size 4 1/2	Depth
Tbg. Size	Depth
Drill Pipe	Depth
Tool	Depth
Cement Left in Csg.	Shoe Joint
Press Max.	Minimum
Meas Line	Displace

Owner **SAME**

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.

Charge To **FRONTIER OIL CO.**

Street **1437 N. FRANKLIN**

City **Russell** State **KS 67665**

The above was done to satisfaction and supervision of owner agent or contractor.

Purchase Order No.

X **Terry W. Piesker**

CEMENT

Amount Ordered	130	50/50	47 gal	370 cc	
Consisting of 10 Gel on side 2 HULLS					
Common	65	SKS	AT	5100	325.00
Poz. Mix	65	SKS	"	2.10	136.50
Gel.	15	"	"	7.25	108.75
Chloride	4	"	"	20.00	80.00
Quickset					
Hulls	2	"	"	14.00	28.00

EQUIPMENT

Pumptrk	No	Cementor	John	Bill
	83	Helper	DATTEN	
Pumptrk	No	Cementor		
		Helper		
Bulktrk		Driver	DUANE	
	117		BRAD	
Bulktrk	56	Driver	JERRY	

Handling	90¢	PER SK	135.90
Mileage	66¢	"	147.54
		34 Miles	
		Sub Total	
		Total	961.69

DEPTH of Job

Reference:	#10 Pump TRK chg	150.00
	#14 1.00 PER Mile	34.00
	4 1/2' Plug	23.50
	Sub Total	
	Tax	
	Total	207.50

Remarks: 2 - HULLS MAX Press 200#
 25 - Cement SHUT IN AT 0#
 10 - Gel
 Release Plug
 105 - Cement.

Floating Equipment

RECEIVED

STATE CORPORATION COMMISSION

FEB 4 1983

2-4-83

Thanks