

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-24113-00-00
Spot: NENWNWNW Sec/Twnshp/Rge: 35-10S-16W
115 feet from N Section Line, 425 feet from W Section Line
Lease Name: LYLE / KASTER Well #: 1-35
County: ROOKS Total Vertical Depth: 3651 feet

Operator License No.: 34132

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	220		150 sx

Op Name: MIKOL OIL LLC

Address: 1407 WASHINGTON CIR
HAYS, KS 67601

Well Type: DH

UIC Docket No:

Date/Time to Plug: 04/26/2013 12:00 AM

Plug Co. License No.: 31548

Plug Co. Name: DISCOVERY DRILLING

Proposal Rcvd. from: TOM

Company: DISCOVERY DRILLING

Phone: (785) 623-2920

Proposed
Plugging
Method:

Ordered 255sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CASE MORRIS

WitnessType: NONE

Date/Time Plugging Completed: 04/26/2013 1:30 PM

KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

1st plug @3585 w/50 sx
2nd plug @1250 w/25 sx
3rd plug @775 w/100 sx
4th plug @275 w/40 sx
5th plug @40 w/10 sx

Rathole 30 sx

Remarks: QUALITY

Plugged through: DP

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 16 2013

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed


6/30/13 (TECHNICIAN)

MAY 07 2013

Form CP-2/3