

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-23092-00-00
Spot: NWSENWSW Sec/Twnshp/Rge: 2-21S-11W
1850 feet from S Section Line, 900 feet from W Section Line
Lease Name: RUGAN G Well #: 1-2
County: STAFFORD Total Vertical Depth: 3500 feet

Operator License No.: 5056
Op Name: F. G. HOLL COMPANY L.L.C.
Address: 9431 E CENTRAL STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3365		
PLG	5.5	3365		
PROD	5.5	3485	0	WITH 225 SX CMT
SURF	8.625	222		WITH 225 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 05/07/2013 8:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND TO 3270' & 5 SX CMT. PERFORATE 5 1/2" @ 600'. PUMP CMT DOWN 5 1/2" & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/07/2013 10:45 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 3270' & 5 SX CMT ON TOP OF SAND WITH DUMP BAILER.
PERFORATED 5 1/2" @ 600. RAN TBG TO 620'. CIRCULATED CMT TO SURFACE UP
THE 5 1/2" CASING & THE 8 5/8" X 5 1/2" ANNULUS USING 160 SX CMT. PULLED
TBG OUT OF HOLE. TOPPED OFF HOLE WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3342	3346		
3327	3346		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: TBG

KCC WICHITA

MAY 22 2013

RECEIVED

District: 01

RECEIVED

MAY 16 2013

KCC DODGE CITY

Signed

Richard W. Lacey
5/30/13

(TECHNICIAN)

Boyer