

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-171-30069-00-00  
Spot: NWNW Sec/Twnshp/Rge: 11-20S-33W  
4611 feet from S Section Line, 4624 feet from E Section Line  
Lease Name: WASINGER Well #: 1  
County: SCOTT Total Vertical Depth: 4785 feet

Operator License No.: 33476  
Op Name: FIML NATURAL RESOURCES, LLC  
Address: 410 17TH ST STE 900  
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1250		
CIBP		2325		WITH 2 SX CMT
PROD	4.5	2678	0	WITH 130 SX CMT
SURF	8.625	241		WITH 225 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/14/2013 8:30 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: EDDIE ABERCROMBIE-AB Company: \_\_\_\_\_ Phone: (620) 793-2816

Proposed Plugging Method: Set CIBP @ 2450' w/ 2sxs cmt. Set another CIBP @ appx. 2000'-2100'. Test casing. If casing ok perf above plug and squeeze w/ 100-150sxs cmt. Dig out cellar, mix cement until 200-300# is reached.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/14/2013 11:30 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2325' WITH 2 SX CMT. (FILL UP @ 2340') CIBP @ 1250'. TEST CASING TO 700#. HOLDING. PERFORATE @ 1200'. BREAK DOWN @ 2500#. INJECTION RATE 2 1/2 BPM @ 1250#. MIX & PUMP 80 SX CMT WITH 50# HULLS IN LAST 20 SX AT 2 BPM @ 1000#. LEFT 20 SX CMT INSIDE THE 4 1/2" & 60 SX CMT OUTSIDE THE 4 1/2". PERFORATE @ 270'. CIRCULATE CMT TO SURFACE WITH 80 SX CMT, LEAVING THE CASING & ANNULUS FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
2622	2627		

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: CSG

RECEIVED  
KANSAS CORPORATION COMMISSION

MAY 20 2013

CONSERVATION DIVISION  
WICHITA, KS

District: 01

RECEIVED

MAY 15 2013

KCC DODGE CITY

Signed

*Ken Jehlik*  
SPO/LS

(TECHNICIAN)

AWT