

15-077-19039-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Well Plugging Authority,
issued March 3, 1967.

RECEIVED
MAR 8 1967
3-8-67
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name H. C. Bennett

Complete Address: 1212 Union National Bank Bldg., Wichita, Kansas

Lease Name Hufford Well No. # 1

Location C SW NW Sec. 19 Twp. 31 Rge. 6 (E) (W) W

County Harper Total Depth 4378'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Flint Engineering and Construction Company

Address: Box 950, El Dorado, Kansas License No. 547

Operation Completed: Hour 10:15AM Day 6th Month March Year 1967

The Above well was plugged as follows:

247' of 8 5/8" surface pipe, cemented with 150 sacks. 4378' of 4 1/2" long
string, cemented with 125 sacks. Top perferation 4283'. Bottom of the
hole was sanded to 4275', and cemented with 5 sacks. 3880' of 4 1/2" long
string was recovered from the hole. 15 sacks of Gel-Mud and 25 sacks of
cement was pumped in the surface pipe, through an 8 5/8" swage, to a
pressure of 300 lbs. Plug was pumped down to 170'. This was left swaged
in over the week-end. Monday morning the top of the cement was tagged at
173'. Fluid in the hole was bailed down to 40', bridge plug and rock bridge
from 40' to 30', and cemented with 10 sacks to the base of the cellar. This
cement was pumped by Halliburton Cementing Company.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving
Well Plugging Supervisor

INVOICED
DATE 3/8/67
INV. NO. 4881-W