

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 2 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Walters Drlg. & Mill Drlg.

Complete Address: 400 Insurance Bldg., Wichita, Kansas

Lease Name Bryant Well No. 1

Location C SW SW Sec. 9 Twp. 18 Rge. (E) (W) 20

County Rush Total Depth 4170

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated:

Plugging Contractor: Rains & Williamson

Address: Wichita, Kansas License No.

Operation Completed: Hour 7P Day 30 Month 4 Year 1969

The Above well was plugged as follows:

RTD 4170' 8 5/8 csg set at 218' cwc Gmt. Mat. 50-50 poz cmt W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 70 sk cmt

thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cmt thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulla and 10 sk cmt to base

of cellar. Plugged rat hole with 2 sk cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Red F. Moseley
Well Plugging Supervisor

DATE 5/2/69
INV. NO. 4906-W