

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -165-20, 747-0000 (of this well)

Operator's Full Name HERBERT G. DAVIS INC.

Complete Address 3030 LIBERTY TOWER - OKLAHOMA CITY, - OKLA.

Lease Name WEBS. Well No. # 1-29

Location SW - SW - NW. Sec. 29 Twp. 18 Rge. 20 (E) (W) W

County RUSH Total Depth 4300 FE.

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor RAINS & WILLIAMSON OIL CO. INC.

Address 435 PAGE COURT 220^W DOUGLAS WICHITA^{KS.} License No.

Operation Completed: Hour 2:15 PM Day 24th Month JAN Year 1980

The above well was plugged as follows:

8 5/8" 600 FE. SD. CUC. 1330^{SE} COMMON 2% GEL. - 3% CA-CL.

ORDERED 85^{SE} 50/50 BOZMIX 6% GEL + 8 5/8" PLUG.

SPOTTED WITH DRILL STEM. - WITH HEAVY MUD BETWEEN ALL PLUGS

1ST PLUG. @ 610 FE W/ 50^{SE} Cmt. 1-29-80

2ND PLUG. @ 200^{FE} W/ 20^{SE} Cmt.

3RD PLUG. → SOLID BRIDGE MULL'S PLUG. → @ 40 FE W/ 10^{SE} Cmt.

5^{SE} IN RAT HOLE

CEMENTED BY ALLIED CEMENTING

I hereby certify that the above well was plugged as herein stated.

Signed: William Schubert
Well Plugging Supervisor

INDEXED
DATE 1-29-80
INV. NO. 1428-W