

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

4-26-77

API Number 15 - 165 - 20,632-0000 (of this well)

Operator's Full Name Pickrell Drilling Co.

Complete Address 205 Litwin Bldg., Wichita, Kansas

Lease Name Janke "A" Well No. 1

Location NE NW SE Sec. 33 Twp. 18 Rge. (E) (W) 20

County Rush Total Depth 4320'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 5 P Day 24 Month 4 Year 1977

The above well was plugged as follows:

RTD 4320' 8 5/8 csg set 213' cwc 150 sk. Plg Mat. 50-50 poz 2% total gel.

Gunned pits, circulated heavy mud, set 50 sk cmt plug at 500' thru drill pipe.

Heavy mud to 185' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

DATE 4-26-77

INV. NO. 5038-W