



KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 25 1969  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Pickrell Drilling Company

Complete Address 705 4th Nat'l Bldg., Wichita, Kansas 67202

Lease Name Frank "A" Well No. 1

Location C SW NE Sec. 32 Twp. 18 Rge. (E) (W) 20

County Rush Total Depth 4258

Abandoned Oil Well XX Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated     

Plugging Contractor Russ Casing Pulling

Address Box 1082 Great Bend, Kansas License No. 623

Operation Completed: Hour 1:30P Day 24 Month 9 Year 1969

The above well was plugged as follows:

Total Depth 4258' 8 5/8 csg set at 273' cwc 180 sk.

5 1/2 csg set at 4249' cw 100 sk cmt.

Filled 5 1/2 csg W/sd (4100-4249) Dumped 5 sk cmt W/dump bailer. (4060-4100)

Hole in 5 1/2 csg at app. (800'-900') No pipe recovered.

Pumped down 5 1/2 csg W/200 sk 50-50 poz cmt W/6% total gel.

Pumped down annulus (8 5/8 - 5 1/2) W/100 sk 50-50 sk poz cmt W/6% total gel.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9/26/69

INV. NO. 535-W

Signed: Geo F. Messing  
Well Plugging Supervisor