

15-165-20095-0000

KANSAS

Form CP-3
Rev. 6-9-67

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202DEC 26 1967
12-26-67

Operator's Full Name Nadel-Gussman

Complete Address 625 Union Center Wichita, Kansas

Lease Name Tammen Well No. 1

Location NW NW NE Sec. 34 Twp. 19 Rge. 18 (E) (W) X

County Rush Total Depth 4036

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor John O. Farmer, Inc.

Address Russell, Ks. License No.

Operation Completed: Hour 9:30 A Day 23 Month 12 Year 1967

The above well was plugged as follows:

RTD 4036' 8 5/8 csg set at 317' cwc 160 sc Cementing Material 50-50POZ W/6% gel.

Gunned pits, circulated heavy mud, set cementing plug at 660' and displaced 70 sc cem.

thru drill pipe. Heavy mud to 315' set cementing plug and displaced 20 sc cement thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base

of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo T. Massey
Well Plugging SupervisorDATE 12/27/67
INV. NO. 6975-W