

# Kansas Corporation Commission

## District Plugging Report

API Well Number: 15-073-23127-00-00

Spot: NENWNE Sec 23 Twp 26 S Rng 12 ☒ E / ☐ W  
5132 Feet from ☐ N / ☒ S Line of Section  
1712 Feet from ☒ E / ☐ W Line of Section

GPS: Lat: 37.778560 Long: 96.058110 Date: 8/9/11

Lease Name: Lois Roberts Well #: (ROB 01)

County: Greenwood Total Vertical Depth: 1440 feet

Operator License No: 101 String Size Depth Pulled Comments  
 Op Name: State of Kansas SURF - Casing 8.000 110 0 From Intent  
 Address 1: 130 S. MARKET  
 Address 2: \_\_\_\_\_  
 City: WICHITA  
 State: KS Zip Code: 67202 - \_\_\_\_\_

Well Type: OG - Oil & Gas (oil) UIC Docket No.: \_\_\_\_\_ Date/Time to Plug: 2/12/13 / \_\_\_\_\_  
 Plug Co License No.: 3097 Plug Co. Name: K-W OIL WELL SERVICES, INC.  
 Proposal Revd from: Robert Kepy Company Name: K-W Phone: (620) 431-2285

Proposed  
Plugging  
Report:

Drill and wash to TD. Stage plugs, 500 ft to surface.

Plugging Proposal Received By: FRANK GUILFOYLE Witness Type: COMP - Complete 100%  
 Date/Time Plugging Completed: 2/12/13 / \_\_\_\_\_ KCC Agent: FRANK GUILFOYLE, Tony Anderson

Actual Plugging Report:	Perfs:	Top	Bottom	Thru
Move in and set up drill rig. Gel pit water and keep gelled until done. Drill and wash through cave and wood to 810 ft. Pull drill steel and run 2 3/8" to 625 and hit cave. Wash to 960 ft and hit hard. Couldn't break through. Pull pipe and run drill steel in. Drill and wash to 1440 ft. Stage 5 barrel plugs at 1440 ft, 1375 ft, 1080 ft, and fill from 530 ft to surface. Pump total of 352 sacks of cement. Well plugged.				

Remarks: Contract # 11782. Cat III. Control # 20130028-001. GPS by Mike Heffern. Reg Sec.  
NAD83

Plugged Thru: DP - Drill Pipe RECEIVED KANSAS CORPORATION COMMISSION  
 Plugged Due to Compliance Issue: ☐ Yes ☒ No  
 District: 03 APR 02 2013  
 CONSERVATION DIVISION WICHITA, KS  
 (Technician)  
 Form: District Plugging Report - \_\_\_\_\_