

Kansas Corporation Commission
District Plugging Report

API Well Number: 15-037-01680-0008
 Spot: NW Sec 31 Twp 28 S Rng 22 E / W
4636 Feet from N / S Line of Section
3125 Feet from E / W Line of Section
 GPS: Lat: 37.570840 Long: 95.044530 Date: 10/6/11
 Lease Name: ZUMMALLEN CR CO Well #: ZUM OW1
 County: Crawford Total Vertical Depth: 375 feet

Operator License No: 101
 Op Name: KANSAS CORPORATION COMMISSION
 Address 1: 130 S MARKET
 Address 2: _____
 City: WICHITA
 State: KS Zip Code: 67202 - _____

Well Type: OG - Oil & Gas (Oil) UIC Docket No.: _____ Date/Time to Plug: 1/25/12 / _____
 Plug Co License No.: 33749 Plug Co. Name: KWS
 Proposal Revd from: MIKE KEPLEY Company Name: KWS Phone: (620) 431-9212

Proposed Plugging Report: **CLEAN OUT WELLS TO BOTTOM. PUMP FULL OF PORTLAND CEMENT, INSIDE AND OUTSIDE OF CASING. IF CEMENT IS PRESENT IN THE ANNULUS, CASING SHOULD BE PERFORATED IN AT LEAST 2 INTERVALS, UNLESS WELL IS DOCUMENTED AS ALT. 2 COMPLETION.**

Plugging Proposal Received By: TONY ANDERSON Witness Type: COMP - Complete 100%
 Date/Time Plugging Completed: 1/25/12 / _____ KCC Agent: TONY ANDERSON

Actual Plugging Report:	Perfs:	Top	Bottom	Thru
DUG OUT SURFACE AND REMOVED 8' OF 3/4 INCH PIPE. RAN A BIT TO 350' AND PULLED OUT. PERFED AND THEN WASHED TO 375' AND PLUGGED WITH 29 SACKS OF CEMENT. THE LOCATION WAS THEN RESTORED.		<u>250</u>	_____	_____
		<u>150</u>	_____	_____
		<u>75</u>	_____	_____
		_____	_____	_____
		_____	_____	_____

KANSAS CORPORATION COMMISSION
MAR 01 2012
RECEIVED

Remarks: CONTRACT#11782;CONTROL#20120032-001
KAD83

Plugged Thru: TBG - Tubing Plugged Due to Compliance Issue: Yes No

District: 03
Tony Anderson
 (Technician)
 Form: District Plugging Report - _____