

**Kansas Corporation Commission**  
**District Plugging Report**

API Well Number: 15-037-01679-0000  
 Spot: NW Sec 31 Twp 28 S Rng 22  E /  W  
4757 Feet from  N /  S Line of Section  
3423 Feet from  E /  W Line of Section  
 GPS: Lat: 37.571170 Long: 95.045550 Date: 1/17/12  
 Lease Name: ZUMMALLEN CR CO Well #: ZUM OW2  
 County: Crawford Total Vertical Depth: 375 feet

Operator License No: 101 String Size Depth Pulled Comments  
 Op Name: KANSAS CORPORATION COMMISSION  
 Address 1: 130 S MARKET  
 Address 2:  
 City: WICHITA  
 State: KS Zip Code: 67202 -

Well Type: OG - Oil & Gas (OIL) UIC Docket No.: Date/Time to Plug: 1/25/12 /  
 Plug Co License No.: 33749 Plug Co. Name: KWS  
 Proposal Revd from: MIKE KEPLEY Company Name: KWS Phone: (620) 431-9212

Proposed Plugging Report: **CLEAN OUT WELLS TO BOTTOM. PUMP FULL OF PORTLAND CEMENT, INSIDE AND OUTSIDE OF CASING. IF CEMENT IS PRESENT IN THE ANNULUS, CASING SHOULD BE PERFORATED IN AT LEAST 2 INTERVALS, UNLESS WELL IS DOCUMENTED AS ALT. 2 COMPLETION.**

Plugging Proposal Received By: TONY ANDERSON Witness Type: COMP - Complete 100%  
 Date/Time Plugging Completed: 1/30/12 KCC Agent: TONY ANDERSON

Actual Plugging Report:	Perfs:	Top	Bottom	Thru
REMOVED TREE GROWN INTO WELL. WASH TO 410' ON THE 6 3/16" PIPE HAD CORNISH CHECK WITH PIPE LOCATER. PERFED THE 6 3/16" PIPE. RAN 1" BACK IN AND PUMPED 101 SACKS OF CEMENT. THE LOCATION WAS LETER RESTORED.		250		
		150		
		75		

KANSAS CORPORATION COMMISSION  
 MAR 01 2012  
 RECEIVED

Remarks: CONTRACT#11782;CONTROL#20120032-002  
NAD83

Plugged Thru: TBG - Tubing Plugged Due to Compliance Issue:  Yes  No

District: 03  
Tony Anderson  
 (Technician)  
 Form: District Plugging Report -