

Kansas Corporation Commission

District Plugging Report

API Well Number: 15-091-19216-0000
Spot: SWSENW Sec 33 Twp 13 S Rng 23 E/W
2818 Feet from N/S Line of Section
3717 Feet from E/W Line of Section
GPS: Lat: 38.876770 Long: 94.866080 Date: 3/14/12
Lease Name: Olathe Golf Club Well #: OGC 01
County: Johnson Total Vertical Depth: 680 feet

Operator License No: 101
Op Name: STATE OF KANSAS
Address 1: 130 S. MARKET
Address 2:
City: WICHITA
State: KS Zip Code: 67202

Table with columns: String, Size, Depth, Pulled, Comments. Rows include SURF - Casing (8,000, 20, 0, EST.) and PROD - Casing (2,000, 680, 0).

Well Type: RES - Residential Gas Well UIC Docket No.: Date/Time to Plug: 8/20/12 /
Plug Co License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC.
Proposal Rcvd from: Nick Kepley Company Name: KWS Phone: (620) 431-8945

Plug well with portland cement from TD to surface.

Proposed Plugging Report:

Plugging Proposal Received By: FRANK GUILFOYLE Witness Type: COMP - Complete 100%
Date/Time Plugging Completed: 8/20/12 / KCC Agent: FRANK GUILFOYLE

Actual Plugging Report table with columns: Actual Plugging Report, Perfs, Top, Bottom, Thru. Includes detailed text: 'Remove box from well and unhook piping. Run 1" to 680 ft 2". Wash 1" down outside of 2" to 300 ft. Pump portland cement from TD to surface inside 2" and from 300 ft to surface outside 2". Pull pipe and top off well. Pump total of 91 sacks of cement. Well plugged.'

KANSAS CORPORATION COMMISSIC:
OCT 02 2012
RECEIVED

Remarks: Contract No.11782. Control No. 20120048-001. GPS NAD 83 by Taylor Herman 3-14-2012. Reg. Sec.

Plugged Thru: TBG - Tubing Plugged Due to Compliance Issue: Yes No

District: 03

Signature of Frank Guilfoyle (Technician)