

TYPE

AFFIDAVIT OF COMPLETION FORM

ACO-1 WELL HISTORY

SIDE ONE

Compt. _____

Two (2) copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within thirty (30) days after the completion of a well, regardless of how the well was completed.

F Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on Side One will be of public record and Side Two will then be held confidential.

Applications must be made on dual completion, commingling, salt water disposal, injection and temporarily abandoned wells.

C Attach one copy only wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). (Rules 82-2-105 & 82-2-125) KCC# (316) 263-3238.

LICENSE # 5219 EXPIRATION DATE 6/30/83

OPERATOR KIMBARK OIL & GAS COMPANY API NO. 15-165-21,050

ADDRESS 1580 LINCOLN STREET #700 COUNTY RUSH

DENVER, COLORADO 80203 FIELD HARGRAVE

** CONTACT PERSON C. A. HANSEN PROD. FORMATION

PHONE 303/839-5504

PURCHASER LEASE COFFEEN

ADDRESS WELL NO. 1

DRILLING MURFIN DRILLING COMPANY 330 Ft. from NORTH Line and

CONTRACTOR ADDRESS 617 UNION CENTER BUILDING 2310 Ft. from EAST Line of

WICHITA, KANSAS 67202 the NE (Qtr.) SEC 29 TWP 17S RGE 19W.

PLUGGING AS ABOVE WELL PLAT

CONTRACTOR ADDRESS

TOTAL DEPTH 4014 PBTD

SPUD DATE 12/22/82 DATE COMPLETED 8/1/83

ELEV: GR 2163 DF 2165 KB 2168

DRILLED WITH (CORRY) (ROTARY) (CORRY) TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE

Amount of surface pipe set and cemented 349' DV Tool Used? NO

THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil, Gas, Shut-in Gas, Dry, Disposal, Injection, Temporarily Abandoned, OWWO. Other

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

A F F I D A V I T

C. A. HANSEN, being of lawful age, hereby certifies that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.

SUBSCRIBER APPEARED TO BEFORE ME this 24th day of JANUARY 1983.



MY COMMISSION EXPIRES SEPTEMBER 15, 1986

** The person who can be reached by phone regarding any questions concerning this information.

(Signature of C. A. Hansen)

(Signature of Christine Pickart)

1580 LINCOLN STREET #700 DENVER, COLORADO 80203 STATE CORPORATION COMMISSION

RECEIVED JAN 27 1983 CONSERVATION DIVISION WICHITA KANSAS

SIDE TWO

ACO-1 WELL HISTORY

OPERATOR KIMBARK OIL & GAS COMPANY LEASE COFFEEN

SEC. 29 TWP. 17S RGE. 19W

FILL IN WELL INFORMATION AS REQUIRED:

WELL NO. 1

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
<input checked="" type="checkbox"/> Check if no Drill Stem Tests Run.				
Surface dirt and shale	0	715	Topeka	3214 (-1046)
Shale & sand	715	1374	Heebner	3523 (-1355)
Anhydrite	1374	1400	Toronto	3542 (-1374)
Shale	1400	3615	Lansing	3569 (-1401)
			Base Kansas	3848 (-1680)
			City	
Shale & Lime	3615	4014	Arbuckle	3994 (-1826)

If additional space is needed use Page 2, Side 2

Report of all strings set— surface, intermediate, production, etc. CASING RECORD New ~~XXXX~~

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8 5/8	24	349	Regular	200	3% CaCl ₂ , 2% gel

LINER RECORD


PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used



Date of first production DRY Producing method (flowing, pumping, gas lift, etc.)

Estimated Production -I.P. Oil Gas Water % Gas-oil ratio
 bbls. MCF bbls. CFPB

Disposition of gas (vented, used on lease or sold)

Perforations