


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Map

Rush County. Sec. 34 Twp. 19 Rge. 17 (E) (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW NW SE
Lease Owner BEN F. BRACK OIL COMPANY, INC.
Lease Name CONARD Well No. 1
Office Address 309 Brown Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed March 1, 1951 19
Application for plugging filed March 1, 1951 19
Application for plugging approved March 1, 1951 19
Plugging commenced March 1, 1951 19
Plugging completed March 1, 1951 19
Reason for abandonment of well or producing formation No show of
commercial quantity.
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes, orally

Name of Conservation Agent who supervised plugging of this well Mr. C. D. Stough
Producing formation Arbuckle Depth to top 3903 Bottom 3935 Total Depth of Well 3935 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface, Shale and Shells	--	0	585	8-5/8"	850.73'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 30' feet to 250' feet for each plug set.

First Plug set at 250' with 15 sacks of cement
Second Plug set at 30' with 10 sacks of cement. Hole filled and levelled.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to BEN F. BRACK OIL COMPANY, INC.
Address 309-10 Brown Building
Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

Emil E. Bowers (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Emil E. Bowers

309-10 Brown Building, Wichita 2, Kansas
(Address)

Subscribed and sworn to before me this 26 day of March 1951

My commission expires November 1, 1954

28-5091-s

8-50-10M

Notary Public.

PLUGGING
FILE SEC 34 T 19 R 17 W
BOOK PAGE 65 LINE 8

BBN P. BRACK OIL COMPANY, INC.
300-10 BROWN BUILDING
WICHITA 2, KANSAS

CONARD #1

SW SW NE

Sec. 34, Twp. 19, Rg. 17W
Rush County, Kansas

Commenced: February 12, 1951

Completed: March 1, 1951

TOTAL DEPTH: 3935'

WELL LOG

Surface	0'
Lime, Shale	60
Shale, Shells	510
Shale, Shells	585
Sand, Shale	705
Red Bed, Shale	848
Red Bed	1200
Anhydrite	1225
Shale, Shells	1565
Shale	1660
Salt, Shale	1850
Shale	1875
Shale, Lime Shells	2035
Pt. Wiley	2055
Lime, Shale	2335
Lime	2525
Lime, Shale	2570
Broken Lime, Shale	2670
Lime, Shale	3445
Broken Lime	3500
Lime, Shale	3570
Lime	3635
Lime, Shale	3705
Lime	3880
Red Bed, Chert	3900
Lime	3935 T D

CASING RECORD

8-5/8" 850.73'

FORMATIONS

Lansing	3568
Karnaton	3827
Conglomerate	3869
Arbuckle	3903

To the best of my knowledge, the above
is a correct and true statement of all
formations and where found.

RECEIVED
STATE CORPORATION COMMISSION
3-29-51
MAR 29 1951

BBN P. BRACK OIL COMPANY, INC.

CONSERVATION DIVISION
Wichita, Kansas

By *Emil E. Bowers*
Emil E. Bowers

Witnessed:

Charles R. Evans

March 19, 1951

