

15-165-28953-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Rush SEC. 32 TWP. 17S RGE. 17W E/W
Location as in quarters or footage from lines:
N/2 NW SW

		<u>32</u>	

Lease Owner Hummon Corporation
 Lease Name Edwards Well No. 1
 Office Address 400 One Main Place, Wichita, Kansas 67202
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
 Date Well Completed 11/25/81
 Application for plugging filed 12/3/81
 Plugging commenced 11/25/81
 Plugging completed 11/25/81
 Reason for abandonment of well or producing formation Dry Hole

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant
Producing formation _____ Depth to top _____ bottom _____ T.D. 3642'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
		<u>0'</u>	<u>1098'</u>	<u>8-5/8"</u>	<u>1091.69'</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Plugged with 70 sacks cement at 1050';
40 sacks cement at 540'; plug and 10 sacks
cement at 40'; and 5 sacks cement in
rat hole.

RECEIVED
STATE CORPORATION COMMISSION


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Allied Cementing Co.

CONSERVATION DIVISION
Wichita Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

John D. Knightley Agent (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) [Signature]
221 S. Broadway, Wichita, KS 67202
(Address)



SUBSCRIBED AND SWORN TO before me this 3rd day of December, 19 81

Stella J. Lipp
Notary Public.

My Commission expires: March 12, 1983

Hummon Corporation
400 One Main Place
Wichita, Kansas 67202

-

Edwards #1
N/2 NW SW Sec. 32-17S-17W
Rush County, Kansas

Contractor: D. R. Lauck Oil Company, Inc.
221 S. Broadway, Suite 400
Wichita, Kansas 67202

Commenced: November 17, 1981
Completed: November 25, 1981

Drillers Log

Post Rock	70
Blue Shale	480
Sand	715
Shale	1095
Anhydrite	1131
Shale	1810
Shale & Shells	2670
Shale	2970
Shale & Shells	3090
Lime & Shale	3330
Lime	3616
Chert	3621
Shale & Lime	3642 RTD

RECEIVED
STATE CORPORATION COMMISSION

DEC 1 1981

CONSERVATION DIVISION
Wichita, Kansas