

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Rush SEC. 32 TWP. 17S RGE. 17W E/W
 Location as in quarters or footage from lines:

NE NW NW

Locate Well
 correctly on above
 Section Platt.

Lease Owner Rains & Williamson Oil Company, Inc.
 Lease Name Miller #1 Well No. _____
 Office Address 435 Page Court Bldg. 220 W. Douglas Wichita, Ks. 67202
 Character of Well (Completed as Oil, Gas or Dry Hole): _____
 Date Well Completed _____
 Application for plugging filed _____
 Plugging commenced 3-8-83
 Plugging completed 3-9-83
 Reason for abandonment of well or producing formation Depleted

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant

Producing formation _____ Depth to top _____ bottom T.D. 3622'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	1095'	none
				4-1/2"	3595'	2966'

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

Bottom was already squeezed with 50 sacks cement. Shot casing @2987', pulled a total
 of 68 joints of 4-1/2" casing. Plugged well with 5 sacks hulls, 2 sacks gel, 65 sacks
 cement, released plug and displaced with 100 sacks cement.

Plugging Complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 347 Chase, Ks. 67524
 (Address)

SUBSCRIBED AND SWORN TO before me this 14th day of March, 19 83

My Commission expires:



J. H. Hoover
 STATE CORPORATION COMMISSION
3-16-83
MAR 16 1983

CONSERVATION DIVISION
 Wichita, Kansas

15-165-20662-0000

DRILLER'S LOG

COMPANY: Rains & Williamson Oil Co., Inc.

SEC. 32 T. 17S R. 17W

WELL NAME: Miller #1

LOC. NE NW NW

COUNTY: Rush

RIG NO. #7

TOTAL DEPTH 3622'

ELEVATION 2010 GL 2015 KB

COMMENCED: 12-18-77 COMPLETED: 1-1-78

CONTRACTOR: Rains & Williamson Oil Co., Inc.

CASING RECORD:

SURFACE: 8 5/8" @ 1095' w/250 sx. 60/40 poz., 2% gel, 2% cc. and 200 sx. common, 2% gel, 3% cc.

PRODUCTION: 4 1/2" @ 3595' w/125 sx. 60/40 poz., 2% gel, 10% salt.

LOG

(Figures Indicate Bottom of Formations)

Shale	520
Sand	720
Shale	1970
Lime	2246
Lime & Shale	2427
Shale & Lime	2766
Lime	3622
<u>ROTARY TOTAL DEPTH</u>	<u>3622</u>

STATE CORP. RECEIVED
JAN 1 2 1978
CONSERVATION COMMISSION
Wichita, Kansas

STATE OF Kansas)
COUNTY OF Sedgwick) SS:

I, Wilson Rains, President of Rains & Williamson Oil Co., Inc.
upon oath state that the above and foregoing is a true and correct copy of the log of the
Miller #1 well.

Wilson Rains
Wilson Rains

Subscribed and sworn to before me this 9 day of January, 1978.

My Appointment Expires:
10-4-79

Juanita M. Green
Juanita M. Green

