

15-1165-00374-0000

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH


Locate well correctly on above  
Section Plat

Rush County. Sec. 32 Twp. 17S Rge. 17W (E) (W)  
Location as "NE/CNW/SW" or footage from lines SW SW NW  
Lease Owner Imperial Oil of Kansas, Inc.  
Lease Name Miller Well No. 1  
Office Address Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed October 26, 1957  
Application for plugging filed October 28, 1957  
Application for plugging approved October 28, 1957  
Plugging commenced November 4, 1957  
Plugging completed November 4, 1957  
Reason for abandonment of well or producing formation No commercial quantities of oil found.

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Don Truan, Gorham, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3636 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	9-28-57	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged back with crushed rock to 3358',  
dumped 5 sacks cement at 3358' with dump  
bailer. Top of cement, 3325'. Filled hole  
with mud to 450', set rock bridge, dumped  
25 sacks cement. Top of cement, 375'.  
Filled hole with mud to 40', set rock  
bridge, dumped 10 sacks cement for cap.

11-9-57  
NOV 9 1957

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Miller Casing Pulling Company  
Address Great Bend, Kansas

STATE OF KANSAS, COUNTY OF Sedgwick, ss.  
Raymond L. Bacon (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. IMPERIAL OIL OF KANSAS, INC.

(Signature) By: Ray L. Bacon V-P  
780 Fourth National Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of November, 1957  
Luetta M. Duxson  
Notary Public.

My commission expires December 19, 1960

PLUGGING  
FILE SEC 32 T. 17 R. 17W  
BOOK PAGE 57 LINE 34

DRILLER'S LOG

Imperial Oil of Kansas, Inc.  
780 Fourth National Building  
Wichita 2, Kansas

Miller No. 1  
SW SW NW Sec. 32-17-17W  
Rush County, Kansas

Total Depth: 3636'

Elevation: 2021' RB  
Production: D & A

Commenced: 9-28-57 Completed: 10-26-57

Contractor: Imperial Oil of Kansas, Inc.  
Wichita, Kansas

Casing Record: Set 8-5/8" Surface Pipe at 1106' with 500 sacks cement.

Figures indicate bottom of formations:

Shale & Sand	495'		<u>TOPS</u>	
Dakota Sand	740'	Anhydrite		1101' (✓ 920)
Shale, Shells, & Sand	865'	Heebner		3266' (-1245)
Shale & Shells	1101'	Toronto		3285' (-1264)
Anhydrite	1133'	Lansing		3321' (-1300)
Shale & Shells	1780'	Granite Wash		3605' (-1584)
Shale & Lime	2575'	Granite		3636' (-1614)
Shale & Shells	2875'	Total Depth		3636' (-1615)
Shale & Lime	3275'			
Lime	3613'			
Granite Wash	3630'			
Granite	3632'			
Granite Wash	3636'			
Total Depth	3636'			

We hereby certify this to be a correct and accurate log of the above described well as shown on the daily drilling reports.

PLUGGING  
HLE SEC 32 T 17 R 17W  
BOOK PAGE 57 LINE 34

IMPERIAL OIL OF KANSAS, INC.

By: Ray L. Bacon  
Vice-President

Subscribed and sworn to before me this 21st day of October, 1957.

My Commission Expires:

December 19, 1960

11-9-57

Louella M. Duncan  
Notary Public