

15-165-00161-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

Rush County. Sec. 5 Twp. 19 Rge. (E) 20 (W)

Location as "NE/CNW/SW" or footage from lines. NE NE SW

Lease Owner Sunray Mid-Continent Oil Company

Lease Name Chess Irvin Well No. 1

Office Address P.O. Box 195, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed November 11 19 55

Application for plugging filed November 9 19 55

Application for plugging approved November 14 19 55

Plugging commenced November 11 19 55

Plugging completed November 11 19 55

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundage

Producing formation Depth to top Bottom Total Depth of Well 4480 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	302'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Dumped 30 sax cement & 1/2 sax hulls on bottom. Filled with mud to 290'.
Dumped 10 sax cement & 1/2 sax hulls.
Filled with mud to surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Stickle Drilling Company
Address Tulsa, Oklahoma

STATE OF Kansas, COUNTY OF Barton, ss.

C. C. Shreve (employee of owner) or other representative of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)



Box 195, Great Bend, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of November, 19 55

My commission expires December 24, 1956

Notary Public.



Sunray Mid-Continent Oil Company
Tulsa 2, Oklahoma

Tulsa, Oklahoma
November 23, 1955

CONTRACTOR: Stickle Drilling Company
Drilling Commenced: October 24, 1955
Drilling Completed: November 10, 1955

Irvin #1 SW/4 Sec. 5-
18S-20W, Rush County,
Kansas.

DRILLERS LOG

Sandy Shale & Post Rock	0-65
Sand & Shale	65-304
Shale & Red Bed	304-660
Sand & Shale	660-1025
Shale & Red Bed	1025-1075
Red Bed & Shale	1075-1150
Anhydrite	1150-1175
Shale & Lime	1175-1420
Shale & Shells	1420-2130
Lime & Shale	2130-2220
Lime (Sandy) & Shale Streaks	2220-2320
Lime & Shale	2320-2785
Shale & Lime	2785-2915
Lime & Shale	2915-3000
Shale & Lime	3000-3232
Lime & Shale	3232-3405
Lime	3405-3550
Lime & Shale	3550-3613
Lime	3613-3905
Shale & Lime	3905-3948
Lime & Shale	3948-3977
Lime	3977-4046
Sand & Shale	4046-4048
Lime	4048-4135
Lime Sand & Shale	4135-4165
Lime & Shale	4165-4192
Cherty Lime	4192-4208
Lime & Shale	4208-4242
Cherty Lime & Shale	4242-4287
Shale	4287-4296
Lime w/ Chert	4296-4315
Cherty Lime	4315-4346
Cherty Dolomite	4346-4375
Arbuckle	4375-4420
Lime	4420-4454
Cherty Lime	4454-4480 T.D.

I, Frank E. Stickle hereby certify the above to be a true and complete Drillers Log of Sunray Mid-Continent Oil Company's Irvin #1 SW/4 Section 5-18S-20W, Rush County, Kansas.

Lillian T. Bonham
Notary Public

Frank E. Stickle
Frank E. Stickle

February 13, 1956
My Commission Expires

PLUGGING
WELL NO. 5 T 18 S 20 W
BOOK PAGE 14 LINE 9

11-30-55